

# **Bid Addendum Report**

## **Devchuli Municipality, Nawalparasi-East**

Devchuli Municipality, Nawalparasi-East  
nawalparasi-east  
Devchuli, Nawalparasi East  
Gandaki Province  
Nepal

**Addendum No: 1**

**Published On: 18-12-2020 22:00**

**Invitation No: DEV/NCB/WORKS/03/2077-078**

**Dated On: 23-11-2020 12:00**

## Following changes are made in the bid document

### Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-12-18 22:00:00

## Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Provision for lab test, reconstruction and reallocation of damaged public utility services as per directed by engineer.	PS	1	200000	200000	
2 Construction of Road Works						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earthwork Excavation in all types of Soil 75% mechanical means & 25% manual means as per drawing, specification & instruction of in-charge engineer all complete.	Cum	225.0			
2	Supply & construction of stone soling work with sand by local stone In foundation trench & flooring as per drawing, specification & instruction of in-charge engineer all complete.	Cum	84.38			
3	Supply & construction of (1:3:6) PCC work as per drawing, specification & instruction of in-charge engineer all complete.	Cum	84.4			
4	Supply & construction of RR Stone masonry in (1:4) cement mortar by local stone as per drawing, specification & instruction of in-charge engineer all complete.	Cum	253.13			
5	SUPPLY & CONSTRUCTION OF WOODEN FORM WORK BY LOCAL WOOD FOR RCC AS PER DRAWING, SPECIFICATION & INSTRUCTION OF IN-CHARGE ENGINEER ALL COMPLETE.	Sqm	187.78			
6	COMPACTING ORIGINAL GROUND SUPPORTING SUB-GRADE, LOOSENING OF THE GROUND UPTO A LEVEL A LEVEL OF 500 MM BELOW THE SUB-GRADE LEVEL, WATERED, GRADED AND COMPACTED IN LAYERS AS PER DRAWING, TECHNICAL SPECIFICATION (1003, 1005) & INSTRUCTION OF ENGINEER.	Cum	782.25			

## Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
7	PROVIDING & LAYING GRANULAR SUB-BASE (LOCAL) ON PREPARED SURFACE, MIXING AT OMC, & COMPACTING TO ACHIEVE THE DESIRED DENSITY, COMPLETE AS PER DRAWING, TECHNICAL SPECIFICATION (1201) & INSTRUCTION OF THE ENGINEER.	Cum	782.25			
8	PROVIDING & LAYING CRUSHER RUN MACADAM ON A PREPARED SURFACE, SPREADING & MIXING, WATERING & COMPACTING TO FROM A LAYER OF BASE COURSE AS PER DRAWING, TECHNICAL SPECIFICATIONS (1204) & INSTRUCTION OF THE ENGINEER.	Cum	1173.38			
9	PROVIDING & APPLYING PRIME COAT WITH HOT BITUMEN (INCLUDING CUTTER) (BITUMEN 60/70 GRADE VG 30) ON PREPARED SURFACE OF GRANULAR BASE INCLUDING CLEANING OF ROAD SURFACE & SPRAYING AT SPECIFIED RATE BY MANUAL MEANS, 1 LITER PER SQUARE METER, AS PER TECHNICAL SPECIFICATION (1302) & INSTRUCTION OF THE ENGINEER.	Sqm	7822.5			
10	PROVIDING & APPLYING TACK COAT WITH HOT BITUMEN EMULSION (BITUMEN EMULSION, FAST SET 70% BITUMEN) AT SPECIFIED RATE ON THE PREPARED NON-BITUMINOUS SURFACE BY MECHANICAL MEANS INCLUDING CLEANING, 0.75 LITER PER SQUARE METER, AS PER TECHNICAL SPECIFICATION (1302) & INSTRUCTION OF THE ENGINEER.	Sqm	5711.0			

## Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
11	PROVIDING & LAYING (MECHANICAL MEANS) OPEN-GRADED PREMIX CARPET COMPOSED OF 15 MM TO 5 MM AGGREGATES AS WEARING COURSE ON A PREVIOUSLY PREPARED BASE AS PER DRAWING, TECHNICAL SPECIFICATIONS (1311) & INSTRUCTION OF THE ENGINEER.	Cum	142.78			
12	PROVIDING & LAYING SEAL COAT SEALING THE VOIDS IN A BITUMINOUS SURFACE AS PER DRAWING, TECHNICAL SPECIFICATION (1310) & INSTRUCTION OF THE ENGINEER.	Sqm	5711.0			
13	PROVIDING REQUIRED MATERIAL & PAINTING LINES, DASHES, ARROWS ETC. ON ROADS IN TWO COATS ON NEW WORK WITH READY MIXED ROAD MARKING PAINT CONFORMING TO NS 408/ IS 164 ON BITUMINOUS SURFACE, INCLUDING CLEANING THE SURFACE ALL THE DIRT, DUST & OTHER FOREIGN MATTER, DEMARCATION AT THE SITE & TRAFFIC CONTROL AS PER DRAWING, TECHNICAL SPECIFICATION (1503) & INSTRUCTION OF THE ENGINEER.	Sqm	64.44			
14	Provide and Instalation of project information board of size 1.80 m x 1.20 m along with iron posts including excavation, concreting, backfilling etc all complete as per DOR standard specification for road and bridge works.	No.	1.0			
15	Insurance for Material, workers, plants, other staff and others etc.	Lumsu m	1.0			